

PLANT SCHEDULE OVERALL - PHASE I


SYMBOL	CODE	BOTANICAL / COMMON NAME	COND	SIZE	QTY
CANOPY TREES					
	ACE AUT	ACER RUBRUM 'AUTUMN FLAME' / AUTUMN FLAME MAPLE	B & B	3" CAL.	2
	CEL OCC	CELTIS OCCIDENTALIS / COMMON HACKBERRY	B & B	3" CAL.	9
	Gm AUT	GINKGO BILOBA 'AUTUMN GOLD' / AUTUMN GOLD MAIDENHAIR TREE	B & B	3" CAL.	3
	LIO WO3	LIQUIDAMBAR STYRACIFLUA 'WORPLESDON' / WORPLESDON SWEET GUM	B & B	3" CAL.	7
	PLA MO3	PLATANUS X ACERIFOLIA 'MORTON CIRCLE' / EXCLAMATION™ LONDON PLANE TREE	B & B	3" CAL.	6
	QUE BIC	QUERCUS BICOLOR / SWAMP WHITE OAK	B & B	3" CAL.	3
	TAX MIC	TAXODIUM DISTICHUM 'MICKELSON' / SHANNEE BRAVE™ BALD CYPRESS	B & B	3" CAL.	7
	TIL RED	TILIA AMERICANA 'REDMOND' / REDMOND AMERICAN LINDEN	B & B	3" CAL.	2
	ULM ACC	ULMUS X 'ACCOLADE' / ACCOLADE ELM	B & B	3" CAL.	5
EVERGREEN TREES					
	JUN BLU	JUNIPERUS CHINENSIS 'BLUE POINT' / BLUE POINT JUNIPER	B & B	6' HT.	6
	JUN HIL	JUNIPERUS VIRGINIANA 'HILLSPIRE' / HILLSPIRE EASTERN REDCEDAR	B & B	6' HT.	6
	PIC ABI	PICEA ABIES / NORWAY SPRUCE	B & B	6' HT.	6
	PIN STR	PINUS STROBUS / WHITE PINE	B & B	6' HT.	4
	THU GR2	THUJA STANDISHII X PLICATA 'GREEN GIANT' / GREEN GIANT ARBORVITAE	B & B	6' HT.	11
UNDERSTORY TREES					
	AME GRA	AMELANCHIER X GRANDIFLORA 'AUTUMN BRILLIANCE' / AUTUMN BRILLIANCE APPLE SERVICEBERRY	B & B	8" CLUMP	7
	SYR WO	SYRINGA RETICULATA 'IVORY SILK' / IVORY SILK JAPANESE TREE LILAC	B & B	2.5" CAL.	2
DECIDUOUS SHRUBS					
	ARO ARB	ARONIA ARBUTIFOLIA / RED CHOKEBERRY	B & B	36" HT.	26
	COR AME	CORYLUS AMERICANA / AMERICAN HAZELNUT	CONT.	36" HT.	35
	COT ACU	COTONEASTER ACUTIFOLIUS / PEKING COTONEASTER	B & B	36" HT.	12
	LOH RIV	DIERNELLA X 'G24B5544' / KODAK® ORANGE DIERNELLA	CONT.	36" HT.	18
	RHU GRO	RHUS AROMATICA 'GRO-LOW' / GRO-LOW FRAGRANT SUMAC	CONT.	#5	28
	ROS FL3	ROSA X 'FLOWER CARPET CORAL' / ROSE	CONT.	24" SPREAD	20
	SYR VUL	SYRINGA VULGARIS / COMMON LILAC	B & B	36" HT.	25
	SYR BL2	SYRINGA X 'BLOOMERANG' / BLOOMERANG LILAC	B & B	36" HT.	6
	VIB BLA	VIBURNUM PRUNIFOLIUM / BLACKHAW VIBURNUM	B & B	36" HT.	25
EVERGREEN SHRUBS					
	JUN FOR	JUNIPERUS CHINENSIS 'SEA GREEN' / SEA GREEN JUNIPER	B & B	24" SPREAD	13
	TAX DEN	TAXUS X MEDIA 'DENSIFORMIS' / DENSE YEW	B & B	36" HT.	22
	THU B14	THUJA OCCIDENTALIS 'BAL JOHN' / TECHNIT® ARBORVITAE	B & B	48" HT.	55
	THU BR2	THUJA OCCIDENTALIS 'BRABANT' / BRABANT ARBORVITAE	B & B	6' HT.	25
	THU WOO	THUJA OCCIDENTALIS 'WOODWARD' / WOODWARD ARBORVITAE	B & B	48" HT.	31
GRASSES					
	CAL KAR	CALAMAGROSTIS X ACUTIFLORA 'KARL FOERSTER' / KARL FOERSTER FEATHER REED GRASS	CONT.	#1	58
	PAN NOR	PANICUM VIRGATUM 'NORTH WIND' / NORTHWIND SWITCH GRASS	CONT.	#1	6
PERENNIALS					
	NEP WAL	NEPETA X FAASSENII 'WALKERS LOW' / WALKERS LOW CATMINT	CONT.	#1	48
TURF GRASS					
	TUR SOD	TURF SOD / DROUGHT TOLERANT FESCUE BLEND	SOD	S.F.	186,826 SF

SITE MATERIALS SCHEDULE STADIUM - PHASE I

	EXISTING DECIDUOUS TREE	64
	EXISTING ARBORVITAE	10
	EXISTING SERVICEBERRY SHRUBS	8
	TRACK SURFACE	55,865 SF
	ARTIFICIAL TURF	104,320 SF
	PAVERS	1,024 SF
	ASPHALT	114,864 SF

PLANT SCHEDULE WEST BUFFER YARD

CODE	BOTANICAL / COMMON NAME	COND	SIZE	QTY
CANOPY TREES				
CEL OCC	CELTIS OCCIDENTALIS / COMMON HACKBERRY	B & B	3" CAL.	3
GIN AUT	GINKGO BILOBA 'AUTUMN GOLD' / AUTUMN GOLD MAIDENHAIR TREE	B & B	3" CAL.	3
LIO WO3	LIQUIDAMBAR STYRACIFLUA 'WORPLESDON' / WORPLESDON SWEET GUM	B & B	3" CAL.	4
TAX MIC	TAXODIUM DISTICHUM 'MICKELSON' / SHANNEE BRAVE™ BALD CYPRESS	B & B	3" CAL.	5
ULM ACC	ULMUS X 'ACCOLADE' / ACCOLADE ELM	B & B	3" CAL.	5
EVERGREEN TREES				
JUN BLU	JUNIPERUS CHINENSIS 'BLUE POINT' / BLUE POINT JUNIPER	B & B	6' HT.	6
PIC ABI	PICEA ABIES / NORWAY SPRUCE	B & B	6' HT.	6
PIN STR	PINUS STROBUS / WHITE PINE	B & B	6' HT.	4
THU GR2	THUJA STANDISHII X PLICATA 'GREEN GIANT' / GREEN GIANT ARBORVITAE	B & B	6' HT.	6
CODE	BOTANICAL / COMMON NAME	COND.	SIZE	QTY
DECIDUOUS SHRUBS				
COR AME	CORYLUS AMERICANA / AMERICAN HAZELNUT	CONT.	36" HT.	15
COT ACU	COTONEASTER ACUTIFOLIUS / PEKING COTONEASTER	B & B	36" HT.	12
SYR VUL	SYRINGA VULGARIS / COMMON LILAC	B & B	36" HT.	25
VIB BLA	VIBURNUM PRUNIFOLIUM / BLACKHAW VIBURNUM	B & B	36" HT.	25
EVERGREEN SHRUBS				
THU B14	THUJA OCCIDENTALIS 'BAL JOHN' / TECHNIT® ARBORVITAE	B & B	48" HT.	30
THU BR2	THUJA OCCIDENTALIS 'BRABANT' / BRABANT ARBORVITAE	B & B	6' HT.	19
THU WOO	THUJA OCCIDENTALIS 'WOODWARD' / WOODWARD ARBORVITAE	B & B	48" HT.	31



LANDSCAPE NOTES:

- PLANT QUANTITIES SHOWN IN THE PLANT SCHEDULE ARE FOR CONVENIENCE ONLY. THE CONTRACTOR IS RESPONSIBLE FOR PROVIDING AND INSTALLING ALL MATERIALS SHOWN ON THE PLAN AND SHOULD NOT RELY ON THE PLANT SCHEDULE FOR DETERMINING QUANTITIES.
- ALL PLANT MATERIALS SHALL BE NURSERY GROWN STOCK AND SHALL BE FREE FROM ANY DEFORMITIES, DISEASES OR INSECT DAMAGE. ANY MATERIALS WITH DAMAGED OR CROOKED/DISFIGURED LEADERS, BARK ABRASION, SUNSCALD, INSECT DAMAGE, ETC. ARE NOT ACCEPTABLE AND WILL BE REJECTED. TREES WITH MULTIPLE LEADERS WILL BE REJECTED UNLESS CALLED OUT IN THE PLANT SCHEDULE AS MULTI-STEM. NO PRUNING TO BE DONE AT THE TIME OF INSTALLATION EXCEPT FOR DEAD OR BROKEN LIMBS.
- ALL LANDSCAPE IMPROVEMENTS SHALL MEET MUNICIPALITY REQUIREMENTS AND GUIDELINES, WHICH SHALL BE VERIFIED BY MUNICIPAL AUTHORITIES.
- ALL PLANTING OPERATIONS SHALL BE COMPLETED IN ACCORDANCE WITH STANDARD HORTICULTURAL PRACTICES. THIS MAY INCLUDE, BUT NOT BE LIMITED TO, PROPER PLANTING BED AND TREE PIT PREPARATION; PLANTING MIX; PRUNING, STAKING AND GUYING, WRAPPING, SPRAYING, FERTILIZATION, PLANTING AND ADEQUATE MAINTENANCE OF MATERIALS DURING CONSTRUCTION ACTIVITIES.
- ALL PLANT MATERIALS SHALL BE INSPECTED AND APPROVED BY THE LANDSCAPE ARCHITECT PRIOR TO INSTALLATION. ANY MATERIALS INSTALLED WITHOUT APPROVAL MAY BE REJECTED.
- THE CONTRACTOR SHALL GUARANTEE PLANT MATERIALS FOR A PERIOD OF ONE YEAR FROM DATE OF ACCEPTANCE BY OWNER. THE CONTRACTOR SHALL OUTLINE PROPER MAINTENANCE PROCEDURES TO THE OWNER AT THE TIME OF ACCEPTANCE. DURING THE GUARANTEE PERIOD, DEAD OR DISEASED MATERIALS SHALL BE REPLACED AT NO COST TO THE OWNER. AT THE END OF THE GUARANTEE PERIOD THE CONTRACTOR SHALL OBTAIN FINAL ACCEPTANCE FROM THE OWNER.
- ANY EXISTING TREES TO BE RETAINED SHALL BE PROTECTED FROM SOIL COMPACTION AND OTHER DAMAGES THAT MAY OCCUR DURING CONSTRUCTION ACTIVITIES BY ERECTING FENCING AROUND SUCH MATERIALS THE CRITICAL ROOT ZONE OF THE TREE TO BE PROTECTED UNLESS SPECIFIED OTHERWISE.
- ALL GRASS, CLUMPS, OTHER VEGETATION, DEBRIS, STONES, ETC. SHALL BE RAKED OR OTHERWISE REMOVED FROM PLANTING AND LAWN AREAS PRIOR TO INITIATION OF INSTALLATION PROCEDURES.
- THE CONTRACTOR SHALL VERIFY THE LOCATIONS OF ALL UNDERGROUND UTILITIES PRIOR TO INITIATING PLANTING OPERATIONS. THE CONTRACTOR SHALL REPAIR/ REPLACE AND UTILITY, CURBING, ETC. WHICH IS DAMAGED DURING PLANTING OPERATIONS.
- SIZE AND GRADING STANDARDS OF PLANT MATERIALS SHALL CONFORM TO THE LATEST EDITION OF ANSI Z60.1, AMERICAN STANDARDS FOR NURSERY STOCK, BY THE AMERICAN NURSERY & LANDSCAPE ASSOCIATION.
- REFER TO PLAN OF SURVEY FOR LEGAL DESCRIPTION, BOUNDARY DIMENSIONS AND EXISTING CONDITIONS.
- ALL PLANT MATERIAL IN THIS PLANTING PLAN REPRESENTS THE INTENTION AND INTENSITY OF THE PROPOSED LANDSCAPE MATERIAL. THE EXACT SPECIES AND LOCATIONS MAY VARY IN THE FIELD DUE TO MODIFICATIONS IN THE SITE IMPROVEMENTS AND THE AVAILABILITY OF PLANT MATERIAL AT THE TIME OF INSTALLATION. ANY SUCH CHANGES MUST FIRST BE APPROVED BY THE CITY IN WRITING.
- ALL PLANT MATERIAL SHALL BE PLANTED WITH A MINIMUM OF SIX INCHES OF ORGANIC SOIL AND MULCHED WITH A SHREDDED BARK MATERIAL TO A MINIMUM 3" DEPTH.
- ALL BEDS SHALL BE EDGED, HAVE WEED PREMERGENTS APPLIED AT THE RECOMMENDED RATE.
- ALL PARKWAYS SHALL HAVE LAWN ESTABLISHED WITH SEED A GROUND COVER, UNLESS OTHERWISE NOTED.
- ALL LAWN AREAS ON THIS PLAN SHALL BE GRADED SMOOTH AND TOPPED WITH AT LEAST 6" OF TOPSOIL. ALL LAWN AREAS TO BE ESTABLISHED USING SOD. ALL TURF GRASS AREAS ADJACENT TO PAVEMENT OR CURB SHALL BE GRADED FLUSH WITH THAT PAVEMENT AND ALLOW POSITIVE DRAINAGE. ANY SETTLEMENT OF THE TURF GRASS AREAS SHALL BE CORRECTED BY THE LANDSCAPE CONTRACTOR AT THE CONTRACTOR'S EXPENSE PRIOR TO FINAL ACCEPTANCE BY OWNER.
- THIS LANDSCAPE PLAN ASSUMES THE SITE WILL BE PREPARED WITH TOP SOIL SUITABLE FOR THE ESTABLISHMENT OF THE LANDSCAPE MATERIAL PRESENTED ON THIS PLAN. IF ADDITIONAL TOP SOIL IS REQUIRED IT IS UP TO THE LANDSCAPE CONTRACTOR ON THE PROJECT TO PROVIDE, SPREAD AND PREPARE THE SITE AS NEEDED FOR THE IMPLEMENTATION OF THIS LANDSCAPE PLAN.
- CONTRACTORS MUST VERIFY ALL QUANTITIES AND OBTAIN ALL PROPER PERMITS AND LICENSES FROM THE PROPER AUTHORITIES.
- ALL MATERIAL MUST MEET INDUSTRY STANDARDS AND THE LANDSCAPE ARCHITECT HAS THE RIGHT TO REFUSE ANY POOR MATERIAL OR WORKMANSHIP.
- LANDSCAPE ARCHITECT IS NOT RESPONSIBLE FOR UNSEEN SITE CONDITIONS.
- ALL PLANTINGS SHALL BE SPACED EQUAL DISTANT, BACK FILLED WITH AMENDED SOIL IN A HOLE TWICE THE FOOTBALL DIAMETER, WATERED, FERTILIZED, PRUNED, AND HAVE ALL TAGS AND ROPES REMOVED.
- LAWN AND BED AREAS SHALL BE ROTOTILLED, RAKED OF CLUMPS AND DEBRIS.
- REMOVE ALL DEAD AND DISEASED PLANT MATERIAL FROM SITE AND DISPOSE OF PROPERLY.
- PLANTS TO BE PLANTED SO THAT ROOT FLARE IS AT THE GRADE OF THE AREA WHERE PLANTED. NO PRUNING TO BE DONE AT THE TIME OF INSTALLATION EXCEPT TO REMOVE DEAD OR BROKEN LIMBS.
- FINAL FOUNDATION PLANTINGS WILL MEET THE VILLAGE FOUNDATION PLANTING REQUIREMENTS (SECTION 5-12-5) ONCE PEDESTRIAN ACCESS IS DETERMINED.

PHASE 1 STADIUM IMPROVEMENTS
BENET ACADEMY
2200 MAPLE AVENUE
LISLE, ILLINOIS

Reserved for Seal:

No.	Date	Description
02/07/25	P.U.D. SUBMITTAL	
04/21/25	P.U.D. SUBMITTAL REVIEW	
06/16/25	P.U.D. RESUBMITTAL	

Design By:	SG	Approved By:	KC	Date:	02/04/25
------------	----	--------------	----	-------	----------

Sheet Title:

P.U.D.
LANDSCAPE
PLAN - PHASE 1

Sheet No:

L100-1